

CITY OF TUCKER

ACKNOWLEDGE RECEIPT OF ADDENDUM #1 FORM

ITB 2024-001

Full Depth Reclamation and Resurfacing

Upon receipt, please print and add to your proposal.

I hereby acknowledge receipt of the supplement pertaining to the above referenced bid.

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ **STATE:** _____ **ZIP:** _____

PHONE: _____ **FAX:** _____

EMAIL ADDRESS: _____

SIGNATURE

DATE

ITB 2024-001
ADDENDUM #1

	QUESTION	ANSWER
1	Where can contractors drop equipment at throughout the project the night before? Single file down one side of a street coned off?	Equipment needs to be stored on public property. This could be along one side of a street or in a cul de sac or in a public parking lot. Coordinate with the city inspector.
2	Where can spoils be hauled off from curb clean up, etc? City yard? Other?	The City has no facility for excess spoils. Contractor is to haul off.
3	Proposal references GADOT Spec. governs. Is the 315 Cement Stabilized Reclaimed Base Construction the spec. to use?	Yes.
4	Is a mix design required for this project like GADOT 315 calls out?	The contractor's plant is to submit a mix design.
5	Is there a georeport or core findings of the roads to see how much asphalt there is and what is underneath?	No cores have been done.
6	Businesses with multiple entrances. Can we close off one entrance during the process? i.e. McDonald's and QT at Roger Marten Way.	Yes, as long as one full access driveway remains open at all times. Coordinate with the inspector.
7	Hydrant and meter access. Will the city provide a meter and can we hook on to any hydrants in the project?	The contractor is responsible for obtaining a water meter from DeKalb County Watershed Management.
8	Is there a bidders list available?	A plan holders list is available on BidNet.com posting for this ITB.
9	Will the City of Tucker require the finished asphalt to be flush with the lip of the curb & gutter?	The finished asphalt level should be the same as existing since we are removing the same depth that we're replacing.
10	What will be the average depth of the Patching?	Patching depth will vary from 4"-6" in depth. To be determined by the City inspector.
11	The pay item for Milling states that the depth will be 2". Several of these roads that are not receiving FDR have asphalt above or in the gutter. Will the contractor only mill 2" on these roads also?	Yes.

ITB 2024-001
ADDENDUM #1

12	The proposal states that Hessian Ct. and Silversmith Ln. only receive Patching. What type of asphalt mix should be used for the Patching operation on these roads since it will not be covered up with a topping lift? What will be the depth of Patching on these (2) roads?	19mm Superpave is to be used for patching to a depth of 4"-6" as determined by the City inspector.
13	In the Special Conditions #8 states that Gunstock Dr. and Rosser Terrace have Speed Humps on them that will be removed and replaced. How about the (3) Speed Humps on Florence St.?	Florence Street was inadvertently left out of Special Condition #5. All speed humps are to be milled and replaced. The milling and replacement of the speed humps is considered "incidental" and is to be included in the price of the milling and asphalt pricing.
14	Several of these roads have tree roots that have pushed up the asphalt and the milling, patching and or FDR will remove these tree roots. If the tree happens to die after the work is performed will the contractor be held responsible for removing the tree?	No.
15	Will you be providing a list of streets with their limits as mentioned in the original bid documents?	A list of streets is shown in Exhibit C.
16	On streets where there are tree roots in the road, do you want the contractor to grind through them?	Yes.
17	What will be done with the Concrete Driveway Tie-Ins that owners have placed in the existing C&G if it gets broken in the construction process?	The contractor is responsible for the repair of damaged property including driveway tie-ins, mailboxes, etc.
18	I noticed a lot of uneven curb on Sarah Ln., will the city handle this prior to paving or will the contractor just pave to the existing elevation?	No curb work is anticipated. Pave to existing elevation.
19	On Glenwyck Pl there are is a concrete driveway at the end, how far are we expected to perform FDR?	Perform FDR to the edge of the concrete driveway.